

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Construction of RCC drain at Kalanagara in Kammagondanahalli, in Ward no. 12, in Shettyhalli Sub-Division

Est .Cost Rs. 19.50 Lakhs

Sl No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB-2-2:2 Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. Specification No. KBS 2.1(a)/ 2.3.5, Page No. 5/ Item No. 2.3/ PWD SR 2012-13	Cum ✓							
	RCC Drain		1	217.00	1.20	1.20	312.48		
							312.48	135.00	42185.00
	Basic Rate	125.00 ✓							
	Area Weightage 8%	10.00							
		135.00							
2	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2, Page No. 12/ Item No. 4.2/ PWD SR 2012-13	Cum ✓							
	RCC Drain		1	217.00	1.20	0.15	39.06		
							39.06	4129.92	161315.00
	Basic Rate	3824.00							
	Area Weightage 8%	305.92							
	Total	4129.92							

3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20 mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase lintels retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.6. Page No. 13/ Item No. 4.11/ PWD SR 2012-13	Cum ✓							
	Walls		2x1	217.00	0.15	1.00	65.10		
	Bed		1	217.00	0.90	0.15	29.30		
	Basic Rate	4851.00 ✓					94.40	5239.08	494543.00
	Area Weightage 8%	388.08							
	Total	5239.08							
4	KSRB 4.9.2: providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2012-13	Qtls ✓							
							56.64	7323.48	414780.00
	Basic Rate	6781.00 ✓							
	Area Weightage 8%	542.48							
	Total	7323.48							
5	KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor, cills, plinth including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2, Page No. 17/ Item No. 4.36/ PWD SR 2012-13	Sqm							
	Walls		2x2	217.00		1.00	868.00		

							868.00	565.92	491219.00
	Basic Rate	524.00	✓						
	Area Weightage 8%	41.92							
		565.92							
6	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm	✓						
			1	217.00	0.90		195.30		
	Approved Rate of Precast slab	1600.00	✓						
	Data rate for precast slab of 100MM thick						195.30	1600.00	312480.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 62.20 (P.147 I.18.57/1)	Cum	✓						
	Qty Vide Item No=1						312.48		
	Qty Limited to						312.48	100.35	31358.00
	Basic Rate	25.60							
	Loading and Unloading Charges	67.32							
		92.92							
	Area Weightage @ 8%	7.43							
	Total	100.35							
8	Miscellaneous and unforeseen Charges								2120
								Total	1950000
(Rupees Nineteen Lakhs Five Thousand Only)									

CERTIFICATE

- 1 The Work spot has been inspected and the work found to be necessary
- 2 The Estimate is prepared as per the PWD SR 2012-13
- 3 The Provision made in estimate are adequate and essential
- 4 This area comes under BBMP limits.

Asst Engineer
Ward No-12

Asst Executive Engineer
Shettyhalli Sub-Division
BBMP

Executive Engineer
Dasarahalli Zone
BBMP

no. JC(DH)AS 577/12-13 Date: 31/01/13
Rs. 19.50 lakhs (Rupees Nineteen
Lakhs Fifty thousand only)
Page no. 08F
Sl. No. 57L

no. EE/00/TS/360/12 Date: 05/02/2013
Rs. 19.50 lakhs (Rupees Nineteen
Lakhs Fifty thousand only)
ಇದೇ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಮೇರೆಗೆ ಕೆಲಸ ಮಾಡುವುದಕ್ಕೆ ನಿರ್ದೇಶಿಸಿದೆ
ಇದರಂತೆ ಕೆಲಸ ಮಾಡುವುದಕ್ಕೆ ನಿರ್ದೇಶಿಸಿದೆ
ಇದರಂತೆ ಕೆಲಸ ಮಾಡುವುದಕ್ಕೆ ನಿರ್ದೇಶಿಸಿದೆ